he of Work:Providing and Construction of CC road & drain at Sujatha te front side & Rekha Changappa house road at T.Dasarahalli Ward No 15

Description of Work	Unit	Qty	Rate to be Quoted	
			In figures (Rs)	In Words (Rs
2	3	4	5	6
mtling of existing structures like culverts, Bridges, ining walls and other structure comprising of sonary, cement concrete, wood work,steel work, uding T&P and scaffolding whereever necessary, ting the dismanlet material, disposal of serviceable material and stacking the serviceable terial with all lifts complete as per specification ie/Cement concrete I. By Manual Means C. stressed /Reinforced cement concrete Grade M- & above	Cum	45.60		
cavation for road, drains and similar works - RRB 300-1. Earthwork excavation by manual eans in Ordinary soil involving an average horizontal ow upto 2 meters and an average lift upto 0.5 m, cavated surface leveled and sides neatly dressed, e disposed earth to be leveled neatly after breaking clods complete as per specifications complete as r specifications	Cum	734.40		
oviding, laying, spreading and compacting graded one aggregates to wet mix macadam specifications cluding pre mixing the material with water at OMC in iechanical mix plant carriage of mixed method of oper to site, laying in uniform layers with paver in sub ase / base course on well prepared surface and ompacting with vibratory roller to achieve the desired ensity complete as per specifications. Specification o. 406 with all leads and lifts etc.,	Cum	45.60		
roviding and laying in position plain cement concrete mix 1:4:8 with OPC cement @180 kgs, with 40mm nd down size graded granite metal coarse ggregates @0.85cum and fine aggregates 0.57cum machine mixed, concrete laid in layers not ceeding 15 cms. thick, well compacted, in undation and plinth, including cost of all materials, bour, HOM of machinery, curing complete as per ecifications.	Cum	230.40		

Scanned by CamScanner